

GB1 - GENERAL GARDEN BED PLANT SCHEDULE

CODE	BOTANIC NAME	SIZE	QTY
AO	Aloe 'Ouback Orange'	200mm	20
AS	Austrostipa stipoides	150mm	95
CA	Chrysocephalum apiculatum	150mm	38
DV	Dodonaea viscosa	150mm	30
EG	Eremophila glabra	150mm	57
GG	Grevillea 'Gin Gin Gem'	150mm	83
GO	Goodenia ovata	150mm	38
GV	Goodenia varia	150mm	38
MP	Myoporum parviflorum	150mm	81
LS	Lomandra 'Shara'	150mm	95
PN	Pennisetum 'Nafray'	150mm	487

GB2 - CARPARK / SWALE PLANT SCHEDULE

CODE	BOTANIC NAME	SIZE	QTY
CR	Carex appressa	150mm	196
DB	Dianella brevicaulis	150mm	196
DR	Dianella revoluta var. revoluta	150mm	196
LT	Lomandra 'Tanika'	150mm	196
PP	Poa poiformis	150mm	196

GB3 - REVEGETATION AREA PLANT SCHEDULE

CODE	BOTANIC NAME	SIZE	QTY
DB	Dianella brevicaulis	Tube	330
DR	Dianella revoluta var. revoluta	Tube	330
LT	Lomandra 'Tanika'	Tube	330
PP	Poa poiformis	Tube	330
ET	Enchylaena tomentosa	Tube	330

NOTE: REVEGETATION AREA TO BE INSTALLED DURING JUNE - JULY & MAINTAINED BY COUNCIL - REFER TO SPEC

TREE SCHEDULE

BOTANIC NAME	SIZE	QTY
Banksia integrifolia	45L	7
Brachychiton rupestris	100L	4
Callitris gracilis	45L	13
Corymbia citriodora 'Scentuous'	45L	2
Cupaniopsis anacardioides	45L	13

ALL DRAWINGS MUST BE READ IN CONJUNCTION WITH ALL OTHER CONTRACT DOCUMENTS INCLUDING THE PROJECT SPECIFICATIONS, SCHEDULES AND ANY FORMAL INSTRUCTIONS ISSUED DURING THE COURSE OF THE CONTRACT. THE CONTRACTOR MUST VERIFY ALL SETOUT ON SITE AND CHECK THE LOCATION OF ALL SERVICES BEFORE COMMENCEMENT OF WORK. THE CONTRACTOR IS TO NOTIFY OF ANY DISCREPANCIES BETWEEN DRAWINGS OR DISCIPLINES. DRAWINGS ARE NOT TO BE USED FOR CONSTRUCTION UNLESS IDENTIFIED AS 'FOR CONSTRUCTION'. ALL DRAWINGS TO BE READ AT A1 UNLESS OTHERWISE STATED. DRAWINGS ARE INTENDED FOR DIGITAL SETOUT AND DWG FILES WILL BE ISSUED UPON REQUEST. COPYRIGHT LANDSKAP.

LANDSKAP

1:250 / A1 1:500 / A3

0 2 5 10 20m

LEGEND

- EXTENT OF WORKS
- PROPOSED BUILDING EXTENTS
- EXISTING TREE TO BE RETAINED
  REFER TO TREE MANAGEMENT PLAN
- NEW TREE
  REFER TO PLANTING SCHEDULE
- GB1 - GARDEN BED TYPE 01
  REFER MATERIALS SCHEDULE
- GB2 - GARDEN BED TYPE 02
  REFER MATERIALS SCHEDULE
- GB3 - GARDEN BED TYPE 03
  REFER MATERIALS SCHEDULE
- T1 - PUTTING GREEN TURF (MAKE GOOD)
  REFER MATERIALS SCHEDULE
- T2 - EXISTING TURF (MAKE GOOD)
  REFER MATERIALS SCHEDULE
- MULCH ONLY
  REFER MATERIALS SCHEDULE
- RB - ROOT BARRIER
  REFER MATERIALS SCHEDULE
- EXISTING SERVICES
  REFER SURVEY AND OTHER CONSULTANTS DOCUMENTATION

Project Name

Marion Golf Park

Drawing Title

Planting Plan

Architecture & Lead
Intro Architecture

Civil
TMK Engineering

Civil & Services (Carpark)
WGA Engineering

Services
NDY Engineering

Client

City of Marion

Project no. 22.001

Drawing no. 301

Revision T1

REV	DATE	STATUS	DWN	CHK
A	20.06.23	PRELIMINARY COST REVIEW	JC	JB
B	29.06.23	50% REVIEW	JC	AG
C	10.08.23	CLIENT REVIEW	JC	AG
D	20.10.23	100% REVIEW	JC	AG
T1	15.11.23	TENDER	JC	AG