PART A COLUMN SCHEDULE				
Col No.	Station	Length (m) West	Length (m) East	Bracing
1	117.61	0.714	0.509	YES
2	119.15	0.354	0.345	NO
3	120.74	0.674	0.728	YES
4	122.99	0.235	0.175	NO
5	124.44	0.736	0.583	YES
6	125.9	1.133	0.931	YES
7	128.15	0.584	0.495	NO
8	129.74	1.112	1.026	YES
9	131.65	0.649	0.490	NO

PART B COLUMN SCHEDULE				
Col No.	Station	Length (m) West	Length (m) East	Bracing
1	315.02	0.318	0.320	NO
2	316.5	0.253	0.285	NO
3	318.51	0.456	0.131	NO
4	320.73	0.540	0.541	YES
5	323.03	0.740	0.319	YES
6	325.45	0.361	0.271	NO
7	326.59	0.390	0.323	NO

PART C COLUMN SCHEDULE				
Col No.	Station	Length (m) West	Length (m) East	Bracing
1	501.43	0.338	0.290	NO
2	503.18	0.678	0.720	YES
3	505.09	0.159	0.134	NO
4	506.93	0.840	0.660	YES
5	508.4	0.540	0.538	YES
6	510.09	0.207	0.075	NO
7	511.93	0.757	0.801	YES
8	514.85	0.820	0.553	YES
9	515.92	1.514	1.074	YES
10	516.97	1.755	1.328	YES
11	518.89	2.026	1.198	YES
12	520.6	1.711	1.585	YES
13	522.19	1.874	1.681	YES
14	524.85	2.391	1.631	YES
15	526.08	2.312	2.029	YES

PART D COLUMN SCHEDULE				
Col No.	Station	Length (m) West	Length (m) East	Bracing
1	574.97	3.709	2.430	YES
2	576.75	3.267	2.567	YES
3	579.75	3.581	2.274	YES
4	581.49	3.614	2.483	YES
5	582.53	3.085	2.528	YES
6	583.59	2.550	2.321	YES
7	584.95	2.001	1.559	YES
8	587.36	2.478	0.700	YES
9	589.06	1.748	0.315	NO
10	591.47	2.245	1.068	YES
11	594.13	1.462	0.759	YES
12	596.59	1.050	0.171	NO
13	599	1.477	0.711	YES
14	601.06	1.143	0.378	NO
15	603.5	0.938	0.002	NO
16	605.16	1.379	0.592	YES
17	608.16	1.034	0.617	YES
18	609.64	0.882	0.545	YES
19	610.89	0.758	0.468	YES
20	613.49	0.506	0.191	NO
21	616.09	0.356	0.088	NO
22	617.82	0.883	0.524	YES
23	618.44	0.809	0.316	NO
24	619.01	0.758	0.456	YES
25	620.79	0.275	0.837	NO
26	622.95	0.737	0.332	NO
27	623.81	0.538	0.076	NO

NOTE:
1. FOR GENERAL NOTES REFER TO DRAWING J0439-STR-DRG-S0005
2. ALL DIMENSIONS TO BE CONFIRMED PRIOR TO FABRICATION.
3. ALL STRUCTURAL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ARCHITECTURAL, SERVICES AND OTHER CONSULTANTS DRAWINGS.

IFC

CLIENT: ASPECT Studios™

REV:	DATE:	DESCRIPTION:	IVR:	APR'D:
C1	06/07/2022	ISSUED FOR CONSTRUCTION		JA

TITLE:	NAME:
DRAFTER	ESA
DRAFTING CHECK	TM
DESIGNER	LHP
DESIGN CHECK	JA
PROJECT MANAGER	JSH

MARION COASTAL WALKWAY UPGRADE
CELL 5 AND 6
HALLETT COVE, SA 5158
COLUMN SCHEDULES

INNOVIS DESIGN SOLUTIONS

SCALE:	DATE:	PHASE:	SHT SIZE:
	06/07/2022	IFC	A1

DRAWING NUMBER: J0439- STR- DRG- S0055
REVISION: C1

FILE LOCATION: C:\Users\sam.aryanpour\Documents\J0439-STR-MOD-500 Coastal Walking Trail-210309_sam.aryanpour.rvt

©2020, INNOVIS PTY LTD reserves all rights to these drawings, designs and/or any other data contained herein. No part of the said drawings, designs and/or other data may be reproduced, modified, transmitted or used in any form or by any means for any purpose without the prior written consent of INNOVIS PTY LTD other than the sole purpose for which such drawings, designs and/or other data are provided to licensed users on such terms as INNOVIS PTY LTD may prescribe.

PRINT DATE: 6/07/2022 11:57:54 AM

10mm AT A1 0 10 20 30 40 50 60 70 80 90 100